DYNAMIC BEHAVIOUR OF TALL BUILDINGS

Buddhika Edirisooriya

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

This Thesis was submitted to the Department of Civil Engineering for the degree of Master of Engineering In Structural Engineering Design

Department of Civil Engineering

University of Moratuwa

Sri Lanka

93898

Acknowledgement

would like to express my sincere gratitude to Prof. M. T. R. Jayasinghe, without whom this research uld not have been possible. He not only provided direction and guidance through the course of this search, but also inspired me to really learn and understand structural engineering.

addition, I am grateful to the Vice Chancellor, Dean of the Faculty of Engineering and Head of the epartment of Civil Engineering of the University of Moratuwa, for the permission granted for this research ork. Further, I wish to offer my thanks to the Co-ordinator of the Post Graduate research work of ructural Engineering and all the lecturers of the Department of Civil Engineering who helped me in merous ways.

Special thanks go to my parents for their endless support and encouragement and for always believing, d helping me to believe, that I can succeed at anything.

am particularly indebted to Eng. B. A. Dayananda, Managing Director of Dayananda Associates (Pte) d., who encouraged me and helped in numerous ways to make this research a success.

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

wish to thank the librarian and the staff of the library for the co-operation extended to me for this research ork.

addition, my thanks are due to my fellow graduate students for the academic support and Eng. (Ms.) eja Thilakaratne, who read parts of the manuscripts and made constructive criticisms.

ere are many who helped me to succeed in Education from my childhood to date. Finally, I regret the ability to thank individually them, but I offer my heartiest thanks to them all.

Buddhika Edirisooriya
September 2009

Contents

Acknowledgement ii
Contents iii
List of figures vii
List of Tables x

Chapter 1
Introduction
General 1
Objectives 2
Methodology 2
Arrangement of the Thesis 3

Chapter 2
Literature review

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

General 4
Analysis of the structure 5
2.2.1 Geometric non-linearity 8
2.2.1.1 Geometric imperfections 8
2.2.1.2 Accidental eccentricities 8
2.2.2 Material non-linearity 9
Second Order (non-linear) analysis 10
P- Delta effect 10
2.4.1 P-δ Effect 12
2.4.2 Some analytical P-Δ methods 16
2.4.2.1 Method proposed by Schueller W. 16
2.4.2.2 Storey magnifier method 19
2.4.2.3 Multiple-Column magnifier method 21
2.4.2.4 Negative brace method 22
2.4.2.5 "Pseudo" Approaches 23
2.4.2.5.1 "Pseudo Loads" Approach 23
2.4.2.5.2 "Pseudo Displacement" Approach 23

2.4.2.6 The two cycle iterative method 24
2.4.2.7 AISC (American Institute of Steel Construction) Procedure 24
2.4.2.8 Non-Linear Static (Full Newton Rapson) analysis 25
2.5 Requirement for computer based 3-D Modelling for assessment of P-Delta 25
2.6 Structural analysis by software SAP-2000 26
2.6.1 Non-linear analysis in SAP-2000 26
2.6.2 P-Delta analysis in SAP-2000 27
2.6.3 Verification of results of SAP-2000 28
2.7 Summary 30

Chapter 3

Structural forms and loads applied for case study

3.1 General 31
3.2 Geometry of structure 31
3.2.1 Vertical circulation 33
3.2.2 Service core and Shear walls 34
3.2.3 Different floor usages and applied gravity loads 34
3.2.4 Initial member sizing 35
3.3 Properties of structure 35
3.4 Loading to be applied on the structures 36
3.4.1 Dead and Imposed (Live) loads 36
3.4.2 Lateral loads 36
3.4.2.1 Wind speeds to be adopted in Sri Lanka 36
3.4.2.2 Wind Load Calculation 38
3.5 Structural forms for Case Study 38
3.5.1 Case Study (1) – 30 Storeyed building with hard zoning lift arrangement 38
3.5.2 Case Study (2) – 40 Storeyed building with soft zoning lift arrangement 41
3.5.3 Case Study (3) – 40 Storeyed building with hard zoning lift arrangement 42
3.5.4 Case Study (4) – 45 Storeyed building with hard zoning lift arrangement 45

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

Chapter 4

Computer modelling and case study

4.1 General 48

4.2 Computer modelling 48

4.2.1 Load cases and Combinations 48

4.2.2 Element selection for study 49

4.3 Results and Observation.....51

4.3.1 Results for 30 storeyed building with hard zoning lift arrangement 52

4.3.2 Results for 40 storeyed building with soft zoning lift arrangement 60

4.3.3 Results for 40 storeyed building with hard zoning lift arrangement 68

4.3.4 Results for 45 storeyed building with hard zoning lift arrangement 76

4.4 Comparison and Interpretation of results 85

4.4.1 Effects on beam elements 89

4.4.2 Effects on column elements 90

Chapter 5

Conclusion and future works

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

5.1 Conclusion 91

5.2 Future works 92

Appendices

Appendix A

Calculations – Determination of structural form for 30 storeyed building with hard zoning lift arrangement

A.1 Initial Member Sizing 93

A.2 Design of lifts (using hard zoning technique) and Staircase 96

A.3 Calculation of shear wall properties at ground floor level 99

Appendix B

Calculations – Determination of structural form for 40 storeyed building with soft zoning lift arrangement

B.1 Initial Member Sizing 101

B.2 Design of lifts (using soft zoning technique) and Staircase 105

B.3 Calculation of shear wall properties at ground floor level 109

Appendix C

Calculations – Determination of structural form for 40 storeyed building with hard zoning lift arrangement

C.1 Initial Member Sizing 111

C.2 Design of lifts (using hard zoning technique) and Staircase 115

C3 Calculation of shear wall properties at Ground Floor Level 118

Appendix D

Calculations – Determination of structural form for 45 storeyed building with hard zoning lift arrangement

D.1 Initial Member Sizing 121

D.2 Design of lifts (using hard zoning technique) and Staircase 126

D.3 Calculation of shear wall properties at ground floor level 128

Appendix E

Calculation of wind loads

E.1 Specimen Calculation for wind loads 130

E.2 Wind load on 30 storeyed building with hard zoning lift arrangement 132

E.3 Wind load on 40 storeyed building with soft zoning lift arrangement 133

E.4 Wind load on 40 storeyed building with hard zoning lift arrangement 134

E.5 Wind load on 45 storeyed building with hard zoning lift arrangement 135

References 136

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

List of figures

Chapter 2

Figure 2. 1 Structural System 4
Figure 2. 2 Basic equilibrium equation 6
Figure 2. 3 Fixed ended cantilever beam 7
Figure 2. 4 Action vs. Deformation charts for different analysis types 7
Figure 2. 5 Non-Linear Stress-Strain curve 9
Figure 2. 6 Final stiffness of structure is affected by material stiffness, member Geometry And Structure Geometry 9
Figure 2. 7 P-Delta Effect 11
Figure 2. 8 P-δ Effect 12
Figure 2. 9 Moment magnification factor, A_F (AISC specification) 15
Figure 2.10 P-Δ effect upon the building 16
Figure 2.11 P-Δ effect at Storey Level 19
Figure 2.12 P-Δ effect arising from Load/Frame Asymmetry 20
Figure 2.13 Procedure to determine the second-order deflection, Δ and moment, M for Load/Frame Asymmetry 21
Figure 2.14 Example problem for Result Verification 28
Figure 2.15 Output of P-Δ Analysis from SAP2000 Version 12, for the example problem 29

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

Chapter 3

Figure 3. 1 Wind Zones in Sri Lanka 37
Figure 3. 2 Layout of 30 storeyed building with hard zoning lift arrangement 40
Figure 3. 3 Layout of 40 storeyed building with soft zoning lift arrangement 42
Figure 3. 4 Layout of 40 storeyed building with hard zoning lift arrangement 43
Figure 3. 5 Layout of 45 storeyed building with hard zoning lift arrangement 46

Chapter 4

Figure 4. 1 Local axes of element 50
Figure 4. 2 Selected elements for study.....50
Figure 4. 3 30 Storeyed, Hard Zoning Building – Results of Outer Column – OC 52
Figure 4. 4 30 Storeyed, Hard Zoning Building – Results of Inner Column – IC 53

Figure 4. 5 30 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind X 54
Figure 4. 6 30 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind Y 55
Figure 4. 7 30 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind X 55
Figure 4. 8 30 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind Y 56
Figure 4. 9 30 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[X]-Wind X 57
Figure 4.10 30 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[X]-Wind Y 58
Figure 4.11 30 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[Y]-Wind X 58
Figure 4.12 30 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[Y]-Wind Y 59
Figure 4.13 40 Storeyed, Soft Zoning Building – Results of Outer Column – OC 60
Figure 4.14 40 Storeyed, Soft Zoning Building – Results of Inner Column – IC 61
Figure 4.15 40 Storeyed, Soft Zoning Building – Results of Outer Beam – OB[X]-Wind X 62
Figure 4.16 40 Storeyed, Soft Zoning Building – Results of Outer Beam – OB[X]-Wind Y 63
Figure 4.17 40 Storeyed, Soft Zoning Building – Results of Outer Beam – OB[Y]-Wind X 63
Figure 4.18 40 Storeyed, Soft Zoning Building – Results of Outer Beam – OB[Y]-Wind Y 64
Figure 4.19 40 Storeyed, Soft Zoning Building – Results of Inner Beam – IB[X]-Wind X 65
Figure 4.20 40 Storeyed, Soft Zoning Building – Results of Outer Beam – IB[X]-Wind Y 66
Figure 4.21 40 Storeyed, Soft Zoning Building – Results of Inner Beam – IB[Y]-Wind X 66
Figure 4.22 40 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[Y]-Wind Y 67
Figure 4.23 40 Storeyed, Hard Zoning Building – Results of Outer Column – OC 68
Figure 4.24 40 Storeyed, Hard Zoning Building – Results of Inner Column – IC 69
Figure 4.25 40 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind X 70
Figure 4.26 40 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind Y 71
Figure 4.27 40 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind X 71
Figure 4.28 40 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind Y 72
Figure 4.29 40 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[X]-Wind X 73
Figure 4.30 40 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[X]-Wind Y 74
Figure 4.31 40 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[Y]-Wind X 74
Figure 4.32 40 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[Y]-Wind Y 75
Figure 4.33 45 Storeyed, Hard Zoning Building – Results of Outer Column – OC 76
Figure 4.34 45 Storeyed, Hard Zoning Building – Results of Inner Column – IC 77
Figure 4.35 45 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind X 78
Figure 4.36 45 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[X]-Wind Y 79
Figure 4.37 45 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind X 79
Figure 4.38 45 Storeyed, Hard Zoning Building – Results of Outer Beam – OB[Y]-Wind Y 80
Figure 4.39 45 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[X]-Wind X 81

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

Figure 4.40 45 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[X]-Wind Y 82
Figure 4.41 45 Storeyed, Hard Zoning Building – Results of Inner Beam – IB[Y]-Wind X 83
Figure 4.42 45 Storeyed, Hard Zoning Building – Results of Outer Beam – IB[Y]-Wind Y 84

Appendices

Figure A 3.1 30 Storeyed, Hard Zoning Building – Lift core Arrangement at ground floor level 99
Figure A 3.2 30 Storeyed, Hard Zoning Building – Shear walls at ground floor level 99
Figure B 3.1 40 Storeyed, Soft Zoning Building – Lift core Arrangement at ground floor level.....110
Figure B 3.2 40 Storeyed, Soft Zoning Building – Shear walls at ground floor level.....110
Figure C 3.1 40 Storeyed, Hard Zoning Building – Lift core Arrangement at ground floor level...118
Figure C 3.2 40 Storeyed, Hard Zoning Building – Shear walls at ground floor level 118
Figure D 3.1 45 Storeyed, Hard Zoning Building – Lift core Arrangement at ground floor level...128
Figure D 3.2 45 Storeyed, Hard Zoning Building – Shear walls at ground floor level 128

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

List of Tables

Chapter 2

Table 2.1 Basic Analysis Types..... 5
Table 2.2 Values of ψ and C_m factors for beam-columns under transverse loading 14
Table 2.3 Comparison of End moments 29

Chapter 3

Table 3.1 High rise buildings in Sri Lanka (Dharmawardana,2003) 32
Table 3.2 Grade of concrete and their properties as per BS8110:1985.....35
Table 3.3 Recommended basic wind speed for Sri Lanka 37

Chapter 4

Table 4.1 Result Comparison for Beam Elements 87
Table 4.2 Result Comparison for Column Elements 88
Table 4.3 Moments of resistance for 600mmX300mm beam of Grade 30 concrete 89
Table 4.4 Second moment of area of shear walls at base level 90

University of Moratuwa, Sri Lanka.
Electronic Theses & Dissertations
www.lib.mrt.ac.lk

Appendices

Table E.1 Wind Force on 30 storeyed building with hard zoning lift arrangement 132
Table E.2 Wind Force on 40 storeyed building with soft zoning lift arrangement 133
Table E.3 Wind Force on 40 storeyed building with hard zoning lift arrangement 134
Table E.4 Wind Force on 45 storeyed building with hard zoning lift arrangement 135